



REDLINE



DEMOLITION HAMMERS

PAVING BREAKERS

A Full Line of Demolition Tools to Meet All Your Needs


Whether your demolition tasks require the high impact energy of our 125-R for heavy-duty concrete or asphalt removal or the 17-R for light excavation and demolition work, Kent has a tool to fit your needs. Our Redline series offers a complete line of breakers, rivet busters, clay diggers, trenchers, chippers, tampers, rock drills and sump pumps.

Built to Perform Year After Year

Kent's full line of hand-held air tools are built with one thought in mind - Quality. Our breakers feature complete drop forged construction, four bolt handles for rigid connection to the cylinder, a full control throttle, an efficient valve chest for low maintenance and replaceable front head bushings. Our Teflon - Graphite packing used in our tampers provides cooler operation, needs no adjusting, remains flexible, seals out dirt and lasts longer than conventional seals. Kent's Rock Drills feature swivel air inlets, four pawl construction for positive rotation, safety latch retainer and an automatic oiler for chuck parts.

Backed By Kent

As always, Kent backs their tools with a complete parts inventory and a national distribution network to keep your tools operating at peak performance day after day.



**Model 125-R
Heavy Duty**
90 lb. Class -
Breaks aggregate
concrete, slag or
foundation
removal.

**Model 123-R
Medium Duty**
60 lb. Class -
Excellent for
breaking asphalt,
concrete and brick.

**Model 20-R
Light Duty**
35 lb. Class -
Easy handling in
vertical and hori-
zontal positions.

Model 18-R
Heavy duty tool
used for digging
clay, frozen ground,
concrete or hard pan.

Model 17-R
Ideal for light
excavation and
demolition work.



TRENCHER

TAMPER

RIVET BUSTER

CHIPPERS

FLOOR SCRAPERS



Model 17RT
Long handle allows for easy trenching applications.



Model 6-R
This hard hitting tamper is used for excavation compacting or compacting backfill.



Models: K600, K800 and K1100
Heavy chipping and breaking of concrete, bridgework applications, rivet and bolt head cutting and concrete scaling.



Models: KCB-2, KCB-3, KCB-4




Model: KFS-3 Floor Scraper

| Tool Model | Net Weight (lbs.) | Dimensions (in.) | | | Air Hose Size (in.) | Air Inlet Size (in.) | Standard Chuck (in.) | Optional Chuck (in.) | Bore & Stroke | Blows Per Minute (BPM) | Air Consumption (CFM) |
|-------------------------------|-------------------|----------------------------------|---------|-------------|---------------------|----------------------|----------------------|----------------------|------------------|------------------------|-----------------------|
| | | L | W | D | | | | | | | |
| 125R Breaker | 97 | 28 ³ / ₄ " | 16" | 6" | 3/4" | 3/4" NPT-Male | 1 1/4" Hex x 6" | 1 1/8" Hex x 6" | 2 5/8" x 5" | 1,250 | 77 |
| 125RSP Spike Driver | 87 1/2 | 27 ³ / ₄ " | 16" | 6" | 3/4" | 3/4" NPT-Male | 1 1/2" I.D. | N/A | 2 5/8" x 5" | 1,250 | 77 |
| 123R Breaker | 72 1/2 | 26" | 16" | 6" | 3/4" | 1/2" NPT-Male | 1 1/8" Hex x 6" | 1 1/4" Hex x 6" | 2 1/4" x 5" | 1,400 | 57.7 |
| 20R Breaker | 40 | 26" | 14" | 4" | 3/4" | 1/2" NPT-Male | 1" Hex x 4 1/4" | N/A | 1 7/64" x 5 3/4" | 900 | 49 |
| 18R Clay Digger | 31 1/2 | 22 ³ / ₄ " | 8 1/8" | 4" | 1/2" | 3/8" NPT-Male | 1" Hex x 4 1/4" | 7/8" Hex x 3 1/4" | 1 3/4" x 3 3/8" | 1,550 | 49 |
| 17R Breaker | 34 1/2 | 22 1/2" | 14" | 4 1/2" | 1/2" | 3/8" NPT-Male | 1" Hex x 4 1/4" | 7/8" Hex x 3 1/4" | 1 3/4" x 3 3/8" | 1,550 | 49 |
| 17RT Trencher | 46 | 32 1/4" | 14" | 4 1/2" | 1/2" | 3/8" NPT-Male | 1" Hex x 4 1/4" | 7/8" Hex x 3 1/4" | 1 3/4" x 3 3/8" | 1,550 | 49 |
| 6R Tamper | 40 | 49 ³ / ₈ " | 3" Body | 5 3/4" Butt | 3/4" | 1/2" NPT-Female | N/A | N/A | 1 1/2" x 5 1/2" | 800 | 38.5 |
| K600 Mini Rivet Buster | 23 | 17" | 8" | 5" | 1/2" | 7/8-24 NPT-Female | 11X Heavy Shank | N/A | 1.4" x 2 3/4" | 1,560 | 40 |
| K800 Rivet Buster | 31 | 22" | 6 3/4" | 3" | 1/2" | 7/8-24 NPT-Female | 11X Heavy Shank | N/A | 1 3/16" x 8" | 800 | 32 |
| K1100 Rivet Buster | 34 | 25" | 6 3/4" | 3" | 1/2" | 1/2" NPT-Female | 11X Heavy Shank | N/A | 1 3/16" x 11" | 750 | 35 |
| KCB 2* Chipper | 18 | 14 ³ / ₄ " | 8 1/8" | 3 1/8" | 1/4" | 7/8-24 NPT-Female | .680 Rd. or .580 Hex | Ball-Type Retainer | 1 1/8" x 2" | 2,300 | 29.75 |
| KCB 3* Chipper | 19 | 16" | 8 1/8" | 3 1/8" | 1/4" | 7/8-24 NPT-Female | .680 Rd. or .580 Hex | Ball-Type Retainer | 1 1/8" x 2 1/2" | 2,200 | 31.5 |
| KCB 4* Chipper | 20 | 17" | 8 1/8" | 3 1/8" | 1/4" | 7/8-24 NPT-Female | .680 Rd. or .580 Hex | Ball-Type Retainer | 1 1/8" x 4" | 1,800 | 33.25 |
| KFS-3 Floor Scraper | 17 | 60" | 2 1/2" | 2 1/2" | 1/2" | 1/2" NPT-Female | .580 Hex | N/A | 1 1/2" x 1 1/2" | 3,850 | 12 |
| KFS-1 Floor Scraper | 14 | 60" | 2 1/2" | 2 1/2" | T/C | 1/4" NPT-Female | .590 Hex | N/A | 1 3/16" x 1 1/2" | 2,300 | 7 |

* Note: Chippers and Rivet Busters supplied with Swivel and Retainer

ROCK DRILLS



Used for drilling blast holes, bolt and conduit hole drilling in concrete.

| Model & Type | Chuck Size (in) | Net Weight Weight | Overall Length (in) | Air Hose Size (in) | Air Consumption | Blows Per Minute (BPM) | Bore & Stroke (in) |
|--------------|-----------------|-------------------|---------------------|--------------------|-----------------|------------------------|--------------------|
| RD-7B | 7/8 x 4 1/4 | 16.5 lbs. | 19 in. | 3/8 | 36 | 2900 | 1 15/16 x 1.89 |
| RD-112D | 7/8 x 3 1/4 | 30 lbs. | 19 in | 3/4 | 60.0 | 2100 | 2 1/8 x 1 25/32 |
| RD-519 | 1 x 4 1/4 | 51 lbs. | 20.5 in. | 3/4 | 92.2 | 2300 | 3 x 2 |
| RD-22D | 1 x 4 1/4 | 59 lbs. | 24 in. | 3/4 | 124.0 | 1800 | 2 3/4 x 2 3/4 |
| RD-75 | 1 x 4 1/4 | 61 lbs. | 24 in. | 3/4 | 115.0 | 2100 | 2 5/8 x 3 |



711 Lake Street
 Kent, Ohio 44240
 330-673-5826
 Toll Free: 1-800-527-2282 (East Coast)
 1-800-624-1616 (West Coast)
 Fax: 330-677-1616